

805. ROAD DELINEATORS

805.1. General

The work covers supplying and fixing roadway indicators, hazard markers and object markers.

805.2. The design, materials to be used and the location of the road delineators shall conform to Recommended Practice for Road Delineators, IRC: 79, and to relevant drawings or as otherwise directed by the Engineer.

805.3. Measurements for Payment

The measurement shall be made in numbers of delineators fixed at site.

805.4. Rate

The Contract unit rate for Road Delineators shall be payment in full compensation for furnishing all labour, materials, tools, equipment for preparing, supplying and fixing at site and all other incidental costs necessary to complete the work to these Specifications.